Sl. No.	Items of work	Per	Rate	Quantity	Tender rate in	
					Figures	Words
			Rs. a. p.		Rs.	Rs.
4	Burnt brick in clay superstructure ..	C. ft.	0 3 0	1,533		
4a	Burnt brick in mortar superstructure ..	,,	0 4 0	510		
5	Stone slabs 4″ thick roughly dressed and fixed in mortar	S.ft.	0 8 0	21		
6	Chunam plastering (2 coats)	Sqr.	3 0 0	43.14		
7	Cement pointing with thread lining ..	,,	4 0 0	2.07		
8	White and colour washing 2 coats (as per plastering and pointing)	,,	0 4 0	44.64		
9	Roofing with first class Mangalore tiles on T. W. reepers 2″×1″ including wood oiling	,,	24 0 0	15.00		
10	Ridge tiles set in mortar and cement pointed complete	R.ft.	0 8 0	78		
11	Ventilating tiles big size, fixed, etc., complete	,,	2 0 0	16		
12	T. W. work wrought and put up including 2 coats of wood-oiling	C.ft.	5 0 0	65.13		
13	T. W. doors battened 1″ thick shutters with all fixtures complete (frames 3″×4″ or flat iron clamps 1″ long and 2″ wide ..	S.ft.	1 2 0	156		
14	T. W. battened windows 1″ thick shutters and $\frac{5}{8}$″ iron bars with all fixtures complete ..	,,	1 8 0	75		
15	T. W. shelves with shutters and shelf planks, etc., complete	,,	1 2 0	60		
16	Chocolate painting, 2 coats	Sqr.	4 0 0	7.52		
17	Constructing sink in bath rooms complete	Each	5 0 0	4		
18	Providing stone mortar and pestle complete	,,	5 0 0	4		
19	Flooring with 3″ lime concrete (1 : 3) and $1\frac{1}{2}$″ cement concrete (1 : 2 : 4) on top with $\frac{1}{2}$″ cement plastering (1 : 3) on top complete (with red ochre colour)	Sqr.	20 0 0	5.5		
20	Do (without red ochre colour)	,,	18 0 0	2.5		
21	Levelling ground, etc.	As per actual work.				
22	Providing and fixing T. W. planks with T. W. pegs, complete	S.ft.	0 8 0	100		
23	Constructing 'V' shaped drain 4″ in lime concrete as per specification	R.ft.	0 8 0	70		
24	Chunnam patty brick in lime mortar 3″×6″ plastering, etc., complete	,,	0 4 0	125		
25	Excavating soakage pits 5′×5′×6′ and filled with brickbats of $1\frac{1}{2}$″ to 2″ size well burnt and covered with 1″ thick red earth connecting the drain to it with a galvanised pipe 3″ to 4″ dia. and an iron grating at the entrance, etc., complete..	As per actual work.				

B. TIRUMALACHAR,
Executive Engineer.

MISCELLANEOUS DEPARTMENTS.

SRI NARASIMHARAJA HOSTEL, BANGALORE.

Notification No. 552, *dated* 20*th February* 1940.

Attention of the public is invited to the tender Notices published in pages 334 to 337, Part VI of the *Mysore Gazette*, dated the 15th February 1940, calling for the supply of provisions, curds and milk vegetables and stationery to the Sri Narasimharaja Hostel, Bangalore, for the year 1940-41.

M. S. RAJAGOPAL RAU,
President.